

MDC

CLEMAR
MINI
DATA
CENTER





The MDC CLEMAR integrates the complete critical infrastructure to ensure high availability and security for your Data Center. With agile deployment and modular growth.

- **Integrated**
- **Compact**
- **Modular**
- **Customizable**
- **Transportable**



SPECIFICATION

	MDC - 03	MDC - 06
Cabinet Features		
Appearance	Rack Indoor Sealed. Robust and Modular	
Dimensions (W x D x H) mm	600 x 1400 x 2000 or 800 x 1400 x 2000	
Total Space	42 U	
Useful Space	24 U	20 U
Static Load	1.200kg / Rack	
Power Distribution		
IT Capability	2,5 kW	5,5 kW
AC Input	220 V / 1F / 60 Hz	
UPS	3,0 kVA	6,0 kVA
Autonomy	> 5 minutes	
Cabling	Passages above and below the rack	
Climatization System		
Type Equipment	Inrack (Installed inside the rack)	
Sensitive Heat Factor	1	
Sensitive Capacity	> 3,5 kW	
Monitoring		
HMI	Touch Screen 10"	
Temperature / Humidity Sensor	Yes	
Smoke Detector	Yes	
Flood Detector	Yes	
UPS	Yes	
Power Distribution	Yes	
Air conditioner	Yes	
Emergency Ventilation	Yes	
Integration with External Equipment	Yes	
Fire Fighting		
Integrated plant with NOVEC extinguishing agent	Optional	

